

- 9. PLANTS SHALL NOT BE BOUND WITH WIRE OR ROPE AT ANY TIME SO AS TO DAMAGE THE BARK OR BREAK BRANCHES. PLANTS SHALL BE HANDLED FROM THE BOTTOM OF THE BALL ONLY. 10. PLANTING OPERATIONS SHALL BE PERFORMED DURING PERIODS WITHIN THE PLANTING SEASON WHEN WEATHER AND SOIL CONDITIONS ARE SUITABLE AND IN ACCORDANCE WITH ACCEPTED LOCAL PRACTICE.
- PLANTS SHALL NOT BE INSTALLED IN TOPSOIL THAT IS IN A MUDDY OR FROZEN CONDITION. DURING SUMMER CONDITIONS ALL PLANT MATERIAL SHALL BE SPRAYED WITH 'WILT-PRUF' OR EQUAL AS PER MANUFACTURER'S INSTRUCTIONS. 11. NO PLANT, EXCEPT GROUND COVERS, SHALL BE PLANTED LESS THAN TWO FEET FROM EXISTING STRUCTURES AND SIDEWALKS. PRUNE ALL MATERIAL OUT OF SIDEWALKS, DRIVES AND VISION TRIANGLES.
- 12. SET ALL PLANTS PLUMB AND STRAIGHT. SET AT SUCH LEVEL THAT, A NORMAL OR NATURAL RELATIONSHIP TO THE CROWN OF THE PLANT WITH THE GROUND SURFACE WILL BE ESTABLISHED. LOCATE PLANT IN THE CENTER OF THE PIT. 13. ALL INJURED ROOTS SHALL BE PRUNED TO MAKE CLEAN ENDS BEFORE PLANTING UTILIZING CLEAN, SHARP TOOLS. IT IS ADVISABLE TO PRUNE APPROXIMATELY 1/3 OF THE GROWTH OF LARGE TREES (2"
- CALIPER AND OVER) BY THE REMOVAL OF SUPERFLUOUS BRANCHES, THOSE WHICH CROSS, THOSE WHICH RUN PARALLEL, ETC. MAIN LEADER OF TREES WILL NOT BE CUT BACK. LONG SIDE BRANCHES, HOWEVER, MUST BE SHORTENED.
- 14. EACH TREE AND SHRUB SHALL BE PRUNED IN ACCORDANCE WITH STANDARD HORTICULTURAL PRACTICE TO PRESERVE NATURAL CHARACTER OF PLANT. PRUNING SHALL BE DONE WITH CLEAN, SHARP TOOLS. 15. TREES SHALL BE SUPPORTED IMMEDIATELY AFTER PLANTING. ALL TREES 4 INCHES AND OVER IN CALIPER SHALL BE GUYED. SMALLER TREES SHALL BE STAKED. GUYING WIRES AND STAKES SHALL BE INSTALLED AS INDICATED. THE LANDSCAPE CONTRACTOR SHALL REMOVE STAKING, GUYING & TREE WRAP AT THE END OF THE ONE YEAR MAINTENANCE & GUARANTEE PERIOD.
- 16. THE TRUNKS OF ALL TREES SHALL BE WRAPPED AS SOON AS POSSIBLE AFTER PLANTING ACCORDING TO STANDARD PROCEDURES AND AS INDICATED. 17. PRIOR TO ANY LANDSCAPE OR IRRIGATION WORK VERIFY EXISTING CONDITIONS.
- 18. PRIOR TO CONSTRUCTION CONTRACTOR TO VERIFY LOCATION OF ALL EXISTING AND PROPOSED UTILITIES. IF CONFLICTS EXIST WITH PROPOSED LOCATIONS OF PLANT MATERIAL CONTACT LANDSCAPE ARCHITECT IMMEDIATELY, DO NOT PLANT MATERIAL.T MATERIAL.
- 19. ALL VINE MATERIAL, TRASH AND INVASIVE SHRUB SPECIES TO BE REMOVED FROM ALL LANDSCAPE AREAS.
- 20. ALL DIMENSIONS ARE B.O.C.(BACK OF CURB) UNLESS OTHERWISE SPECIFIED.
- 21. ALL UTILITIES AND OTHER EXISTING CONDITIONS SHOWN ARE IN NO WAY AS-BUILT CONDITIONS. CONTRACTOR MUST VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION. EXISTING UTILITIES AND OTHER EXISTING CONDITIONS MAY VARY GREATLY DUE TO UNDOCUMENTED CONSTRUCTION.
- 22. ALL PLANTING AREAS TO RECEIVE 4" OF PINE STRAW FOR FINAL TOP MULCHING.
- 23. LANDSCAPE CONTRACTOR TO COORDINATE ON-SITE MEETING WITH ARCHITECT, GENERAL CONTRACTOR & LANDSCAPE ARCHITECT TO REVIEW EXISTING CONDITIONS & PROPOSED WORK PRIOR TO ANY IRRIGATION OR LANDSCAPE INSTALLATION.
- 24. SUBMIT IRRIGATION PLAN FOR APPROVAL PRIOR TO ANY WORK. IRRIGATION TO PROVIDE WATER TO ALL NEW PLANTINGS AND LAWN AREAS.
- 25. PRIOR TO ANY WORK VERIFY FULL APPROVAL FROM OWNER & SULLIVANS ISLAND. 26. SEE SHEET L101 & L102-GRADING & DRAINAGE PLAN FOR ADDITIONAL INFORMATION & PLANTING DETAILS.

TOTAL MITIGATION REQUIRED

PRELIMINARY PLANT SCHEDILLE

T 1/17	PITATILA	IVI I LANI						
QUANTITY CANO	ABBRV OPY TREE	BOTANICAL/COMMON	<u>HEIGHT</u>	<u>SPREAD</u>	CONT	<u>CALIPER</u>	<u>NOTES</u>	TOTAL MITIGATION PROVIDED
<u>8</u>	<u>QUEV</u>	Quercus virginia	<u>13'min.</u>	<u>5'min.</u>	B&B/Cont.	<u>4.5"Min.</u>	Well Formed	<u>36"</u>

PLANT SCHEDULE EXPLANATORY NOTES:

1.THE FOLLOWING PLANT SCHEDULES ARE PREPARED AS A SELECTION OF PLANTING MATERIALS.

2.WHERE AN ABBREVIATION IS SHOWN, FOLLOWING NOTES APPLY:

QUAN - QUANTITY OF PLANT MATERIALS REQUIRED FOR PROJECT. (NOTE: CONTRACTOR RESPONSIBLE TO VERIFY QUANTITIES INDICATED.

<u>Live oak</u>

ABBRV - BOTANICAL ABBREVIATION.

TOTAL MITIGATION PROVIDED

(SEE PLAN & PLANT SCHEDULE)

BOTANICAL/COMMON - NAME OF PLANT MATERIAL

HEIGHT - HEIGHT OF PLANT MATERIAL.

SPREAD - DIAMETER OF PLANT MATERIAL. CONT — CONTAINER TYPE WHICH PLANT MATERIAL IS ENCASED UPON SITE DELIVERY

(SIZE SHALL TAKE PRECEDENCE OVER CONTAINER.)

SPACING- DISTANCE FROM CENTER OF EACH PLANT.(PLAN SHALL TAKE PRECEDENCE OVER SCHEDULE.) CALIPER/DIAMETER OF TRUNK. (REFER TO SPECS FOR MORE SPECIFIC INFORMATION.)

CALIPER SHALL TAKE PRECEDENCE OVER HEIGHT & SPREAD.

NOTES - SPECIFIC NOTES FURTHER SPECIFYING OR DESCRIBING PLANT MATERIAL 3.VERIFY QUANTITIES SHOWN ON PLANT SCHEDULE AND PLANT MATERIAL SHOWN ON PLANTING PLAN. community and job safety

REVIEW SET-NOT FOR CONSTRUCTION

PALMETTO UTILITY PROTECTION SERVICE Don't Dig! Before you call toll free -811-2 hours notice A one call system for

3 PARTS TOPSOIL

4"-6" TOPSOIL MOUND

UNDISTURBED

SUBGRADE

TREE MITIGATION PLAN SHEET NUMBER

SHEET TITLE

LANDSCAPE

ARCHITECTURE

LAND PLANNING

HISTORIC

RENOVATION

CHARLESTON

SOUTH CAROLINA

1.843.412.2894

tomblincompany.com

FAX 1.843.406.2721

(M)

JOB NUMBER

024075

REVISED

/ DHT / 4.30.25